



NOTE:
CENTRES TO BE ADJUSTED TO
FINAL FITTING LAYOUT

Manifold Specification

Project:		14 RUE DU CHATEAU			
Level:		GROUND FLOOR			
Manifold:		1			
Port No.	Loop No.	Room Served	Room Stat.	Spacing mm.	Pipe Length (m)
1	1	CORRIDOR/WC	1	150	65
2	2	BATHROOM	2	150	75
3	3	BEDROOM	3	200	70
4	4	BEDROOM	3	200	70
5	5	CORRIDOR	1	150	55
6	6	UTILITY	4	150	50
7	7	KITCHEN	5	200	70
8	8	KITCHEN	5	200	70
9	9	DINING	5	200	80
10	10	DINING	5	200	80
11	11	DINING	5	200	80

MANIFOLD 1 PIPEWORK SCHEDULE

Coil No	Coil Length (m)	Circuit Numbers
1	50	1/6
2	75	1/1
3	75	1/2
4	75	1/3
5	75	1/4
6	75	1/5
7	75	1/7
8	75	1/8
9	85	1/9
10	85	1/10
11	85	1/11

All loop lengths must be checked prior to and during installation and discrepancies addressed

ROOM STAT POSITIONS TO BE AGREED ON SITE
PIPE CENTRES TO BE ADJUSTED TO SUIT LAYOUT OF KITCHEN FURNITURE ETC.
SUPPLEMENTARY HEATING MAY BE REQUIRED TO HIGH HEAT LOSS AREAS AT DESIGN CONDITIONS

REV.	DRAWING CHANGE DETAILS	DATE

CLIENT
14 RUE DU CHATEAU

PROJECT
GROUND FLOOR
SUGGESTED LAYOUT

DATE
30-11-2017

DRAWN
UFCS

SCALE
1:50 @ A1

DRAWING NO
8150-001

REV